



**ADDENDUM #1**

**DATE: 04/14/2026**

**FROM: Steve Tarnowski Operations Supervisor- Trades  
ARLINGTON HEIGHTS PARK DISTRICT**

**TO: PROSPECTIVE BIDDERS – Camelot Swimming Pool Interior Refinishing**

**SUBJECT: ADDENDUM #1 – Revised Bid Form**

---

**ADDENDA TO BID DOCUMENT**

**The Bid form was changed to include a calculation for linear feet in the areas of:**  
**Sandblasting/Grinding**  
**Concrete Repairs**  
**Painting**  
**Sealants & Caulk**

---

**Please use the attached revised Bid Form when submitting your bid.**

**BIDDERS ARE REQUESTED TO SIGN THIS FORM AS A FORMAL RECEIPT OF THIS ADDENDUM AND TO RETURN IT WITH THE BID FORM.**

**SIGNED BY BIDDER \_\_\_\_\_**

**Bid Form**

**Revised 4/14/26**

**Pg. 1 of 2**

**Camelot Pool**

1005 E. Suffield Dr.  
Arlington Heights, IL 60004

**Company Bidding** \_\_\_\_\_

**Contractor Name** \_\_\_\_\_

**Ph #** \_\_\_\_\_

**Email:** \_\_\_\_\_

**Brief Scope of Work:** Refinishing of Public Pool

**Detailed Scope of Work**

- Sand blast or grind surfaces to remove existing coatings on pool floor, walls, and stairs in both the main pool and dive pool. Main / Lap pool is 5,597sq ft. Dive Pool is 1,529sq ft.
- Mask and protect all stainless steel and drains.
- Clean up and remove all blasting media and debris.
- Grind, cut, route and patch as needed existing cracks within pool floors and walls.
- Proposal includes allowance for minor patching/skim coating of walls after blasting to repair any pitted areas. Major repairs to walls are not included.
- Prep and patch as needed any broken and spalled concrete on pool floor.
- Remove existing sealant from all joints within main pool and dive pool. This includes the horizontal joint on pool wall under the perimeter gutter. Joint between gutter and pool deck is not included.
- Scrape and prep joints for new sealant including backer rod replacement.
- Prime joints with REZI-WELD or an approved equivalent.
- Apply two coats of approved epoxy coating to the entire main pool and dive pool including all floors, walls, stairs, stair edges, lane lines and targets.
- Aggregate to be added for slip resistant finish as required by Owner.
- New paint to be minimum of 5 mils and maximum of 8 mils.
- All work shall be complete by April 30<sup>th</sup> 2027

**Clarifications**

- Pool tile replacement work is not included
- All main drain covers to be removed, stored, and reinstalled by Owner.
- No work is included for the pool deck.
- Concrete repairs are based on current existing and visible conditions.

**Pre-bid Meeting**

- April 14, 2026 at 10am
- 1005 E. Suffield Dr. Arlington Heights, IL 60004
- Submit questions by Monday Wednesday 4-15-26 at 12pm

**Bid Form**

**Revised 4/14/26**

**Pg. 2 of 2**

**Camelot Pool**

1005 E. Suffield Dr.  
Arlington Heights, IL 60004

<b>Bid Sheet</b>	<b>Per Linear Ft.</b>	<b>Main Pool</b>	<b>Per Linear Ft.</b>	<b>Dive Well</b>
Sandblasting/Grinding	_____	\$ _____	_____	\$ _____
Concrete Repairs	_____	\$ _____	_____	\$ _____
Painting	_____	\$ _____	_____	\$ _____
Sealants & Caulk	_____	\$ _____	_____	\$ _____
<b>Total</b>		\$ _____		\$ _____

**Total Base Bid \$** \_\_\_\_\_

**If applicable, Contractor acknowledges Addenda as received:**

**Addenda 1** \_\_\_\_\_

**Addenda 2** \_\_\_\_\_

**Addenda 3** \_\_\_\_\_